


  
**THE TRACK & TURF DOCTOR**
  
**RUNNING TRACK & TURF SPECIALISTS**
  
 740 E Jamaica Ct., Meridian, ID 83642

Project: Kimberly Track Quote

Contact: Robert Stone

Item	Units	Units of Measure	Unit Price	Total Price
Mobilization	1	EA	\$4,620.00	\$4,620.00
Build New Concrete Long Jump Runway with Sand Pits on Each End (See Details Below)	2	LS	\$48,630.00	\$97,260.00
Extend Existing High Hump Area Per Supplied Drawing (See Details Below)	1	LS	\$29,216.00	\$29,216.00
<b>Total</b>				<b>\$131,096.00</b>

**Bid Terms:**

*New Long Jump Work Includes:* Excavation & Offhaul for Runways & Pits, 4" of crushed ¾" Road base under the runway, 4" thick x 4' wide x 20' long concrete runway with a light broom finish, two pits at 10'25' with concrete walls and sand. Two (2) Runways

*Extending High Jump Area Includes:* Excavation & Offhaul of new area (2325 SF), sawcutting along tie-ins, 6" of crushed ¾" roadbase and 2.5" of asphalt furnished and installed.

Price shown does not include performance or payment bond. Add 3% if bonds are required.

Final payment based on quantity installed on job.

Quote does not include; solid rock excavation, traffic control, surveying, design, landscaping/sprinkler line work, any drainage work or design for drainage, testing/inspection fees, utility relocates or SWPPP.